



1
REFLECTED
CEILING PLAN

SCALE : 1/4" = 1'-0"



2
TYPICAL SUSPENDED
GYPSUM BOARD CEILING

SCALE: N.T.S.



KEYED NOTES

- (1) RECESSED LIGHT FIXTURES
- (2) 12 GA HANGER WIRES AT PERIMETER SUPPORTING MAIN RUNNERS AND CROSS RUNNERS @ 1\"/>
- (3) 12 GA HANGER WIRES AT 4'-0\"/>
- (4) CONTINUOUS ANGLE AT WALL EDGE, TYP.
- (5) 12 GA LATERAL BRACING WIRES 2\"/>
- (6) 7/8\" x 26 GA. GALVANIZED HAT FILING CHANNEL AT 2'-0\"/>
- (7) (1) ONE LAYER 5/8\" GYPSUM BOARD
- (8) MAIN RUNNERS, 1 1/2\" COLD ROLLED CHANNELS AT 4'-0\" O.C. MAX.

GENERAL NOTES :

1. CONTRACTOR IS RESPONSIBLE FOR COORDINATING THE INTEGRATION OF ALL NEW DESIGN ELEMENTS WITH EXISTING CONDITIONS. NOTIFY ARCHITECT OF ANY DISCREPANCIES PRIOR TO ANY FABRICATION, CONSTRUCTION OR DEMOLITION.
2. CONTRACTOR IS TO VERIFY WITH OWNER THE EXTENT OF ALL RENOVATION AND DEMOLITION PRIOR TO ANY FABRICATION, CONSTRUCTION OR DEMOLITION. NOTIFY ARCHITECT/OWNER OF ANY DISCREPANCIES PRIOR TO START OF ANY WORK.
3. ALL CEILING HEIGHTS ARE FROM FINISH FLOOR TO FINISHED CEILING.
4. REFER TO ELECTRICAL PLAN FOR LIGHTING INFORMATION.
5. REFER TO MECHANICAL PLAN FOR MECHANICAL SYSTEM INFORMATION.
6. ALL CEILING & SOFFITS ARE 5/8\"/>

CEILING LEGEND

- LIGHTING FIXTURE SEE ELECTRICAL DRAWINGS FOR SPECIFICATIONS AND DETAILS
- ⊙ LIGHTING FIXTURE SEE ELECTRICAL DRAWINGS FOR SPECIFICATIONS AND DETAILS
- LIGHTING FIXTURE SEE ELECTRICAL DRAWINGS FOR SPECIFICATIONS AND DETAILS
- ⊗ CEILING MOUNTED EXIT SIGN SEE ELECTRICAL DRAWINGS
- LINEAR DIFFUSER SEE MECHANICAL DRAWINGS
- 📹 SECURITY CAMERA - SEE ELECTRICAL DRAWINGS FOR SPECIFICATIONS AND DETAILS
- 2\"/>

KEY NOTES

- A WALL TYPES, (SEE SHEET A2.03)
- # DOOR (SEE DOOR SCHEDULE ON SHEET A2.40)
- 1 ELECTRIC POWERED CURTAINS
- 2 PENDANT LIGHT FIXTURE BY OWNER
- 3 COVE FOR LIGHTING SEE DETAIL #3 ON SHEET A4.01
- 4 DIRECTIONAL PIN LIGHTING AS SPECIFIED BY LIGHTING DESIGNER. CONTRACTOR TO INSTALL PER MANUFACTURERS INSTALLATION SPECIFICATIONS
- 5 6\"/>
- 6 12\"/>
- 7 FULL HEIGHT MIRROR
- 8 8\"/>
- 9 CONTRACTOR TO COORDINATE WITH OWNER HEIGHT REQUIREMENTS FOR OWNER SUPPLIED LIGHTING AND PROVIDE BLOCKING.

WESTAR ARCHITECTS

WESTAR Architectural Group/Nevada, Inc
ARCHITECTURE • PLANNING • INTERIOR DESIGN
701 BRIDGER AVENUE SUITE 400 LAS VEGAS, NEVADA 89101
TELEPHONE: (702) 878-0000 FAX: (702) 878-8430
www.wagnarchitects.com

THE PALAZZO

LIDO CASINO RESORT, LLC
STEFANO CANTURI
PROJECT #07087
3265 LAS VEGAS BOULEVARD SOUTH
LAS VEGAS, NV 89109

NUMBER	REVISION DESCRIPTION	DATE
1		
2		
3		
4		
5		
6		
7		

PROJECT NUMBER	07087 LEVEL 117
DRAWN BY:	RC/HB
CHECKED BY:	MM
ISSUE DATE	JULY 16, 2007
SCALE	AS NOTED

PROJECT NUMBER

A3.01

REFLECTED
CEILING PLAN